



M E T R E S

LOAD	DESCRIPTION	LENGTH	WIDTH	HEIGHT	KG	LBS.
1	Substructure (one piece Dreco center-load c/w BOP)	18.60	4.46	4.68	37,610	82,914
2	Drawworks (National 370M c/w Detroit Diesel Series 60)	12.30	3.32	3.21	28,410	62,502
3	Mud Pump #1 (Emsco F-1000 c/w Detroit Diesel Series 2000 engine)	10.70	3.80	3.38	39,390	86,838
4	Mud Pump #2 (Emsco F-1000 c/w Detroit Diesel Series 2000 engine)	10.70	3.80	3.38	38,700	85,318
5	Combo Shack (fuel tank, toolhouse, Accumulator, 2 x Detroit Diesel gensets)	16.20	3.89	3.33	31,210	68,662
6	Doghhouse/Watertank Combo	13.70	3.73	3.95	29,080	63,976
7	Mudtank (c/w King Cobra shale shaker)	17.00	3.96	3.00	30,010	66,022
8	Catwalk (c/w folding pipe rack arms & choke manifold building)	18.30	3.20	3.52	18,300	40,343
9	Derrick (Dreco jackknife triple), crown section (c/w hookblock & drilling line spool)	26.60	3.92	4.05	23,230	51,106
10	Derrick (A-leg section)	17.40	4.75	5.20	13,230	29,106
11	Rig manager's Wellsite	16.10	4.00	3.28	15,850	34,870
12	Matting, Kellybar, Mousehole	10.80	2.46		15,920	35,024
13	Matting, Crown Stand	10.80	2.46		23,426	51,537
14	Matting, V-Door	10.80	2.46		17,280	38,016
15	Drill Pipe Tub	12.82	2.62	1.07	20,454	45,000
16	Drill Pipe Tub	12.82	2.62	1.07	20,454	45,000
17	Drill Pipe Tub	12.82	2.62	1.07	20,454	45,000
18	Drill Pipe Tub	12.82	2.62	1.07	20,454	45,000
19	Drill Pipe Tub	12.82	2.62	1.07	20,454	45,000
20	Drill Collars (165mm x 57mm)				14,108	31,102
21	Drill Collars (165mm x 57mm)				14,108	31,102
22	Misc. Load (flareline tub, 2 x 228mm drill collars, Geronimo weights etc.)					
	Optional Loads					
23	Boiler	10.15	3.13	3.02	15,650	34,430